

**CITY OF COCONUT CREEK
 LYONS ROAD SECTION IV - COCONUT CREEK PARKWAY TO COPANS ROAD
 LANDSCAPING, IRRIGATION, AND PAVERS
 BID NO. 04-13-11-11**

BID SCHEDULE

Note: All irrigation pipes shall meet reclaimed water color and materials specifications All prices shall include labor and materials for complete installation and testing.

Item No.	Description	Est. Quantity	Units	Unit Price	Total Price
1	Mobilization, Demobilization, Bond, NPDES measures, MOT, Permits and Insurance (not to exceed 5% of the Bid Total)	1	LS	\$	\$
2	Surveying and As-Builts	1	LS	\$	\$
3	Excavation	1,135	CY	\$	\$
4	Backfill w/ "Dakota Soil Enhancer"	1,135	CY	\$	\$
5	Irrigation – 4" HDPE DR-11 Mainline w/ Marking Tape (Directional Bore)	1,300	LF	\$	\$
6	Irrigation – 4" HDPE Mainline w/ Marking Tape	400	LF	\$	\$
7	Ductile Iron Mainline Fittings	50	EA	\$	\$
8	Irrigation – 1.5" to 4" HDPE DR-11 Lateral Line (Directional Bore)	250	LF	\$	\$
9	Irrigation – 4" PVC Class 200 Gasketed Mainline w/ Marking Tape (Directional Bore)	3,000	LF	\$	\$
10	Irrigation – Mainline Transition Fittings	29	EA	\$	\$
11	Irrigation – PVC Lateral Pipe	14,000	LF	\$	\$
12	Irrigation – Air Release Valves, Boxes & Identification	2	EA	\$	\$
13	Irrigation – Isolation Valves, Boxes & Identification	4	EA	\$	\$
14	Irrigation – PVC Sleeving	1,000	LF	\$	\$
15	Irrigation – Spray Heads, Rotary Nozzle Heads, & Bubblers	803	EA	\$	\$
16	Irrigation – Hendrickson Flow Control, Spray & Rotary Nozzle Heads	767	EA	\$	\$

Item No.	Description	Est. Quantity	Units	Unit Price	Total Price
17	Irrigation –Zone Valves, Boxes, & Identification Letters	27	EA	\$	\$
18	Irrigation- Pump Station w/ controller, suction line, converter & Electric hook-up	1	LS	\$	\$
19	Irrigation – 2.5" HDPE DR-17 Wire Sleeve (Directional Bore)	2000	LF	\$	\$
20	Irrigation – 2.5" Gray PVC Electric Conduit	3000	LF	\$	\$
21	Irrigation – Control Wire	48,000	LF	\$	\$
22	Irrigation – Clay/Gate (Isolation) Valve Assembly for Reclaimed Water Connection w/ Box & Identification	2	EA	\$	\$
23	Trees: <i>Cordia Boissieri</i> 4" cal., 12'ht.x6' spr., 65 gal.	9	EA	\$	\$
24	Trees: <i>Lagerstroemia indica</i> "Watermelon Red" 14' ht. x 6' spr., 65 gal., multi-trunk	8	EA	\$	\$
25	Trees: <i>Quercus virginiana</i> 8" cal., 27' ht.x14' spr., FG	15	EA	\$	\$
26	Trees: <i>Swietenia mahagoni</i> 5" cal., 18' ht. x 8' spr., FG	7	EA	\$	\$
27	Palms: <i>Veitchia montgomeryana</i> 15' CW., 8' spr., single trunk	8	EA	\$	\$
28	Shrubs/Groundcovers: 1 Gallon	1,664	EA	\$	\$
29	Shrubs/Groundcovers: 3 Gallon	1,169	EA	\$	\$
30	"Flex Edge" Paver Restraint	1,780	LF	\$	\$
31	"Bio Barrier" Root Barrier Edging	750	LF	\$	\$
32	Pavers (includes 10% extra for City of C. Creek)	20,302	SF	\$	\$
33	St. Augustine Sod, (including removal old sod)	73,350	SF	\$	\$

Item No.	Description	Est. Quantity	Units	Unit Price	Total Price
34	Tree Protection	360	LF	\$	\$
35	Tree Removal	10	EA	\$	\$
36	Permits	2	LS	\$	\$
37	Contingencies	1	LS	\$	\$
38	Linear Park Salvage Equip. & Source Cap	1	LS	\$	\$
Bid Total (Items 1 through 38)					\$

BID TOTAL IN WORDS (Items 1 through 38):

ALTERNATE TREE SIZES

Note: Item numbers correspond with like tree species specified in Bid Schedule (Items 23 through 27) above.

Item No.	Description	Est. Quantity	Units	Unit Price	Total Price
23A	<i>Cordia Boissieri</i> 2.5" cal., 8 ht. x 4' spr.	9	EA	\$	\$
24A	<i>Lagerstroemia indica</i> "Watermelon Red" 10' ht. x 5' spr., multi-trunk	8	EA	\$	\$
25A	<i>Quercus virginiana</i> 5" cal., 16' ht. x 8' spr., FG	15	EA	\$	\$
26A	<i>Swietenia mahagoni</i> 4" cal., 12' ht. x 6' spr., FG	7	EA	\$	\$
27A	<i>Veitchia montgomeryana</i> 15' CW., 8' spr., single trunk	8	EA	\$	\$

Company Name: _____
Bidder's Name: _____
Bidder's Title: _____

Completion Time: 180 Calendar Days

Work shall be commenced in accordance with the agreement date and shall be completed within one hundred eighty (180) calendar days as stipulated in the Notice to Proceed.

Bidder: _____

Address: _____

City/State/Zip _____

By: _____

Title: _____

Signature: _____

Attest: _____

(CORPORATE SEAL)