

**DOCUMENT 00310**

**BID PRICE SHEET**

Project: **WINDERMERE/TREE GARDENS SAFE NEIGHBORHOOD  
IMPROVEMENT DISTRICT**  
Bid No.: **P2011-011**

All bid items shall include costs for furnishing to the OWNER, complete, in place and ready for use as described below. This includes materials, equipment, labor, supervision, permit fees, taxes, insurance, bonds, miscellaneous costs, and Contractor's overhead and profit. Costs for materials and equipment shall be included where applicable. Contractor is responsible for verification of all quantities and shall identify discrepancies in writing.

Contractor to review all plans and specifications to provide all necessary equipment to construct signs.

**1. GENERAL ITEMS**

- A. Testing  
Allowance for testing as specified and as ordered by the Owner and Engineer \$18,000
  
- B. Undefined conditions  
Allowance for undefined conditions that occur during the progress of the work. Allowance shall be applied to Change Orders and used only at the Owner's discretion and authorization. \$50,000
  
- C. Allowance for permits and fees \$36,000
  
- D. Mobilization and Demobilization  
Furnish all labor, equipment and materials necessary to mobilize and demobilize the work, including setup of field offices, telephone, fax, etc. and delivery on-site of major equipment necessary to perform work as specified. Fifty percent (50%) for mobilization and fifty percent (50%) for demobilization to be disbursed 30 days after mobilization and 30 days after completion of contract work. \$ \_\_\_\_\_
  
- E. For payment of Construction payment and Performance bond premiums \$ \_\_\_\_\_

**F. SITE PREPARATION AND GRADING**

Site Clearing and Grubbing

Labor, materials, equipment and services to complete the clearing work as indicated in Section 02110.

\$ \_\_\_\_\_

**2. General Materials**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
GM1	utility relocation	EA	2		\$
GM2	pollution prevention silt fence, inlet protection	LS	1		\$
GM3	general demolition	LS	1		\$
GM4	MOT	LS	1		\$
GM5	pavement removal	SY	5,601		\$
<b>SUBTOTAL</b>					

**3. GUARD HOUSE**

(Foundation, Wall, Beams, Caps, Finishes, Waterproofing, Finish building)

\$ \_\_\_\_\_

**4. ELECTRICAL** (Wires, Panels, Conductor, Meter, Assembly, Entire Bldg.)

\$ \_\_\_\_\_

**5. FENCING** (Include electric gates)

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
F1	decorative fencing/ with columns	LF	2039		\$
F2	fence brick column	EA	20		\$
F3	Shadow box fence	LF	105		\$
F4	motorized gates	EA	13		\$
<b>SUBTOTAL</b>					

**6. LIGHTING** (Fixture, Conduit, Brackets, site lighting)

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
L1	street lighting	EA	50		\$

**7. SIGNAGE** (Aluminum Pan, Letters, Logo, Pin Mounts)

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
S1	monument sign	LS	1		\$

**8. LANDSCAPE** (Trees, Shrubs, Groundcovers, Sod, Mulch)

**TREES AND PALMS**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOAL
L1	COCONUT PALM	MIXED HEIGHTS	12		\$
L2	SILVER BUTTONWOOD	10' HT. X 4' SPR.	8		\$
L3	DAHOON HOLLY	8' HT. X 4' SPR.	3		\$
L4	LIVE OAK	12' HT. X 5' SPR.	34		\$
L5	ROYAL PALM	20' O.A. HT. 8' G.W.	3		\$
L6	SABAL PALM	MIXED HEIGHTS	21		\$
L7	GLAUCOUS CASSIA	10' HT. X 4' SPR.	6		\$
L8	SMALL LEAF CLUSIA	24" HT. x 24" SPR.	599		\$
L9	GREEN BUTTONWOOD	24" HT. x 24" SPR.	52		\$
L10	NORMA CROTON	24" HT. x 24" SPR.	100		\$
L11	BLUEBERRY FLAX LILY	18" HT. x 18" SPR.	218		\$
L12	GREEN ISLAND FICUS	18" HT. x 18" SPR.	526		\$
L13	SPIDER LILY	24" HT. x 24" SPR.	219		\$
L14	LILYTURF	12" HT. X 12" SPR.	584		\$
L15	SOD	St. Augustine	6150 SY		
L16	MUHLI GRASS	24" HT. x 24" SPR.	196		\$
L17	DWARF PENTAS	12" HT. X 12" SPR.	36		\$
L18	TRINETTE	24" HT. x 24" SPR.	147		\$
L19	DWARF FAKAHATCHEE	24" HT. x 24" SPR.	229		\$
L20	Remove Existing Trees		23		
L21	Relocate	Palm	1		

**SUBTOTAL**

**9. IRRIGATION** (See Irrigation Details IR.01)

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
I1	irrigation	LS	1		\$

**10. SITE PAVING (parking lot, roads, sidewalks, signage, drainage)**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE /UNIT	TOTAL
D1	18" HDPE	LF	182		\$
D2	18" PHDPE W/ 6' WIDE TRENCH - 19th street	LF	88		\$
D3	INLET W/ FRAME & GRATE - 19th street	EA	2		\$
D4	INLET W/ FRAME & GRATE	EA	4		\$
D5	POLLUTION RETARDANT BAFFLE	EA	6		\$
D6	replace manhole with grate	EA	3		\$
P1	2" ASPHALTIC CONCRETE (TYPE SIII)	SY	4000		\$
P2	8" LIMEROCK BASE	SY	4,200		\$
P3	12" STABILIZED SUBGRADE	SY	4,400		\$
P4	2" ASPHALTIC CONCRETE (TYPE SIII) - 19th st.	SY	300		\$
P5	8" LIMEROCK BASE - 19th street	SY	315		\$
P6	12" STABILIZED SUBGRADE - 19th street	SY	330		\$
P7	5' WIDE 4" THICK CONCRETE SIDEWALK-19th st	LF	85		\$
P8	5' WIDE 4" THICK CONCRETE SIDEWALK	LF	2,795		\$
P9	Concrete pavement	SY	455		\$
P10	5' WIDE sidewalk removal	LF	2,083		\$
P11	TYPE "D" CURB -19th st	LF	290		\$
P12	TYPE "D" CURB	LF	2,700		\$
P14	EARTHWORK	cy	2,000		\$
P16	Wheel stops	EA	49		\$
P17	SIGNING AND PAVEMENT MARKINGS	LS	1		\$
<b>SUBTOTAL</b>					

**11. WATER AND SEWER (fire hydrants, meters, sewer lateral)**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
W1	6" PVC WM (INCLUDING FITTINGS)	LF	28		\$
W2	1" PE WATER SERVICE PIPE	LF	58		\$
W3	FIRE HYDRANT ASSEMBLY	EA	3		\$
W4	6" GATE VALVE	EA	2		\$
W5	5/8" METER ASSEMBLY	EA	1		\$
W6	1" RPZ	EA	1		\$
W7	6" tee - cut in	EA	2		\$
W8	TIE IN TO EXISTING WATER MAIN	EA	1		\$

**SUBTOTAL**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
S1	6" PVC LATERAL SEWER	LF	60		\$
S2	6" CLEAN OUT	EA	1		\$
S3	CUT IN SEWER WYE - CONNECT	EA	1		\$

**SUBTOTAL**

**12. MISCELLANOUS IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE / UNIT	TOTAL
M1	dumpster	EA	1		\$
M2	MOT	LS	1		\$

**SUBTOTAL**

\$

**GRAND TOTAL**

In words

\$ \_\_\_\_\_  
In numbers