

BID FORM

FOR PROJECT NO.: FPN: 420323-1-58-01 , VPN:EN1001

PROJECT NAME: *La Mancha Ave Bike Path*

Item No.	Description	Unit	Quantity	Unit Cost	Cost
101-1	Mobilization	LS	1		
102-1	Maintenance of Traffic	LS	1		
102-3	Commercial Material for Driveway Maintenance (6" Thick)	SY	1801		
110-1-1	Clearing and Grubbing	LS	1		
110-RPB-01	Mailbox (Relocate)	EA	60		
120-RPB-01	Earthwork	LS	1		
285-706	Optional Base, Base Group 06 (Limerock LBR 100, 8" Thick)	SY	2293		
327-70-1	Milling Existing Asphalt Pavement, 1" Avg. Depth	SY	819		
334-1-13	Superpave Asphaltic Concrete, Traffic C (1 1/2" SP-12.5)	SY	2744		
334-RPB-01	Superpave Asphaltic Concrete, Traffic C (SP-9.5, Overbuild)	TN	68		
337-7-32	Asphaltic Concrete Friction Course, Traffic C, FC-9.5, Rubber (1" Thick)	SY	3563		
425-11	Drainage Structure - Modify Existing (6" Core)	EA	11		
425-1-521	Inlets, Ditch Bottom Type C, =<10'	EA	1		
425-71	Inlets Relocation	EA	1		
425-RPB-01	Inlets (8" Inline Drain, ADS Nyloplast)	EA	51		
425-RPB-02	Inlets (8" Drain Basin, ADS Nyloplast)	EA	9		
425-RPB-03	Closed Flume	EA	5		
430-175-101	Pipe Culvert Optional Material, Storm and Cross Drain, Round Shape, Up to 24" (6" Corrugated High Density Polyethylene, ADS N-12 ST IB)	LF	4816		
440-RPB-01	Underdrain	LF	1180		
515-1-2	Pipe Handrail - Guiderail, Aluminum	LF	110		
520-2-9	Concrete Curb, Special (Header Curb)	LF	463		

522-2	Concrete Sidewalk, 6" Thick	SY	187		
522-RPB-01	Detectable Warning (2.0' Wide)	LF	48		
522-RPB-02	Concrete Wheel Stop	EA	4		
570-1-2	Performance Turf, Sod (St. Augustine)	SY	4773		
700-20-11	Single Post Sign, Furnish and Install, Less Than 12 SF	AS	1		
700-20-40	Single Post Sign, Relocate	AS	11		
711-11-111	Thermoplastic Pavement Markings, Standard, White, Solid, 6"	LF	6125		
711-11-125	Thermoplastic Pavement Markings, Standard, White, Solid, 24"	LF	121		
711-11-141	Thermoplastic Pavement Markings, Standard, White, Skip, 6" (2'-4')	LF	384		
711-11-160	Thermoplastic Pavement Markings, Standard, White, Message (Bike Symbol)	EA	12		
711-11-170	Thermoplastic Pavement Markings, Standard, White, Arrow	EA	15		
711-11-211	Thermoplastic Pavement Markings, Standard, Yellow, Solid, 6"	LF	927		
715-4-400	Light Pole Complete, Relocate	EA	1		
908-104-1	Contractor's Sediment and Erosion Control	LS	1		

Pay Item Notes

- 102-3 Modify Standard Specifications for Road and Bridge Construction Section 102-11.4 Commercial Material for Driveway Maintenance:
The quantity to be paid for will be the certified ~~volume area, in cubic yards at 6" thick~~, of all materials authorized by the Engineer, acceptably placed and maintained for driveway maintenance. The ~~volume material~~, which is authorized to be reused, and which is acceptably salvaged, placed, and maintained in other designated driveways will be included again for payment.
- 110-RPB-01 Line item shall consist of all materials and labor necessary to relocate existing mailboxes.
- 285-706 Limerock LBR 100 (8" thick) shall be used. No other base options are acceptable.

TOTAL BASE BID: \$ _____

_____ Dollars

(Amount written in words has precedence)

TOTAL NUMBER OF DAYS: _____ **Days**

_____ Days

Date: _____

The contractor's signature below provides assurance that Addenda #1 through ____ have been received and are included in the estimate in the above bid.

CONTRACTOR: _____